

# ATTIC CONVERSION PROJECT TIMELINE

Projected Schedule & Milestone Tracker

## WEEKS 1-2

### Planning & Permissions

- Architectural Blueprints
- Structural Engineering Report
- Building Permits Approved
- Contractor Procurement

## WEEKS 3-4

### Structural Preparation

- Floor Joist Reinforcement
- Staircase Opening Cut
- Roof Support Bracing
- Dormer Framing (if applicable)

## WEEKS 5-6

### External & Rough-In

- Window/Skylight Installation
- Electrical First-Fix
- Plumbing First-Fix
- HVAC Ductwork

## WEEKS 7-8

### Insulation & Boarding

- Thermal Insulation Layers
- Vapor Barrier Installation
- Plasterboard / Drywall
- Plaster Skimming

## WEEKS 9-10

### Interior Finishing

- Second-Fix Electrics

- Second-Fix Plumbing
- Staircase Installation
- Skirting & Architraves

## **WEEK 11+**

### **Decoration & Handover**

- Painting & Flooring
- Final Building Inspection
- Snag List Completion
- Furniture Installation